
d. The presence of a thicker till cover (greater than 50 feet) should result in a moderate (yellow) aquifer sensitivity

b. The continuous Decorah-Platteville-Glenwood confining unit provides an effective protective barrier. The dark

green indicates very low pollution sensitivity. The orange border indicates high sensitivity along the eroded and

COUNTY ATLAS SERIES ATLAS C-12, PART B, PLATE 9 OF 10 **Sensitivity to Pollution of the Uppermost Bedrock Aquifers**



Well Labels

1 part per million

per million

+ Sinkhole

1.5 If shown, nitrate concentration equals or exceeds

Map Symbols

—— Estimated area of fully saturated Galena aquifer

24.2 If shown, chloride concentration equals or exceeds 12 parts

40,000 If shown, ground-water age in years, estimated by carbon-14

amples contain some chloride from human activities

3000 years before present (carbon-14 age

15

20

10

Tritium Units (TU)

FIGURE 4. Comparison of tritium concentrations to chloride concentrations from well

water samples. Chloride concentrations above

approximately 12 parts per million appear to be partly attributable to human activities from

sources other than halite.

INTRODUCTION

This plate shows the relative sensitivity of the uppermost bedrock aquifers to

The migration of liquid contaminants through unsaturated and saturated earth

RATING MATRIX AND MAP DEVELOPMENT

The sensitivity assessment shown on the map is based on sensitivity classes of

A primary factor in the sensitivity interpretation is the permeability of geologic

The Decorah-Platteville-Glenwood confining unit is expected to be eroded

The other columns of the matrix list other factors affecting vertical flow,

Matrix columns 2 and 3 list factors of the relatively permeable surficial elements.

Alluvium is sediment deposited by low-energy rivers characteristic of the period

SENSITIVITY MAP EVALUATION

Evaluation Data

Ground-water age data (tritium and carbon-14) are used in this and other

The concentrations of commonly occurring contaminants, nitrate and chloride,

The presence of chloride from human activities (road salt, fertilizer, septic tank

and Alexander, 2002). Salt derived from halite deposits typically has chloride to

*Very high locally where sinkholes are present; may imply increased sensitivity over a large area where sinkholes occur in clusters. See Plate 10

FIGURE 2. Sensitivity matrix for sensitivity ratings. Ratings show the influence of combinations of geologic features on the sensitivity of the uppermost bedrock aquifers (except Galena aquifer; see text). Features include the Decorah-Platteville-Glenwood confining unit and various surficial sediments.




FIGURE 1. Geologic sensitivity rating as defined by vertical travel time (Geologic Sensitivity Workgroup, 1991). Ratings are based on the time range required for water at or near the surface to travel vertically into the uppermost bedrock aquifers (sensitivity target). Tritium and carbon-14 studies indicate the relative ages of ground water.

discussed on this plate ranged from 26 to 1 to 784 to 1, with most of the values below 200 to 1. Therefore, chloride contamination from halite is not evident in the county. However, a comparison of tritium unit (TU) values versus chloride concentrations (Figure 4) suggests chloride concentrations above approximately 12 parts per million (ppm) may be partly attributable to human activities from sources other than halite. This graph shows that most of the samples with vintage and mixed tritium characteristics (less than 10 TU) also have low chloride concentrations. One carbon-14 age value is shown for reference indicating natural chloride values may be at least as high as 7 ppm. This natural chloride population is the cluster of data points in the lower left portion of the graph. Most of the water samples with recent tritium characteristics (greater than 10 TU) also have higher chloride values. The line between the two populations appears to be at about 12 ppm.

Evaluation by Area

Decorah Plateau. In the Decorah plateau area, 16 ground-water samples were collected from the St. Peter-Shakopee aquifer for analysis of tritium concentrations. As predicted by the model, all of the samples had tritium concentrations indicating vintage water (greater than 50 years old). Two samples analyzed for carbon-14 age yielded values of 3000 years and 40,000 years before present; these values indicate the presence of very old water in this setting. In addition, none of the sampled wells contained elevated concentrations of chloride (values greater than 12 ppm).

Zumbrota-Goodhue. A large area of moderate to high sensitivity is shown in the southeastern part of the county surrounding the towns of Goodhue and Zumbrota. Smaller moderate to high sensitivity areas are also located in the north-central portion of the county mostly in the Vasa, Welch, and Featherstone townships. The main protection for the uppermost bedrock aquifer in these areas is the overlying clayey till that can be greater than 200 feet thick in some locations. In the Zumbrota-Goodhue area, 14 well water samples were collected for tritium analysis. As predicted by the model, most (11 of 14) of these samples contained mixed water indicating some infiltration of recent water. In addition, seven of these samples contained elevated nitrate concentrations ranging from 1.2 ppm to 5 ppm, and three had elevated chloride concentrations from 15 ppm to 24 ppm. Although some of the nitrate values may represent naturally occurring concentrations, some infiltration of nitrate-contaminated

water since presettlement times is indicated. As explained above, tritium, nitrate, and chloride values in water samples from this area suggest a moderate to high sensitivity. Since the main protective layer in this area is glacial till, the area sensitivity is largely related to the till permeability. Extensive fractures within till sediments may have caused this higher than expected ensitivity. Other chemical evidence collected from the underlying aquifers suggests that ground-water residence time within these till units is not long compared to

ground-water residence times in thick till regions elsewhere in Minnesota.

The interaction of water with various geologic materials as it infiltrates can alter the chemistry of the water. These chemistry changes can reveal information about ground-water residence times and recharge sources. Table 1 shows the proportion of barium and strontium from rocks in the Prairie du Chien Group and from glacial sediment (till and loess) samples; barium and strontium are much higher in the glacial sediments than in the Prairie du Chien rocks. If the till was an effective confining unit, water might move so slowly through the till that it could leach elevated concentrations of barium and strontium into the underlying Prairie du Chien units. Ekman and Alexander (2002) show elevated (greater than 0.2 ppm) concentrations of these constituents associated with mostly mixed and vintage water samples from ill areas of northwestern Minnesota. Figure 5 shows relatively low (approximately 0.1 ppm) mean concentrations of these constituents in water samples from area wells ompleted in the Prairie du Chien and St. Peter aquifers. These relationships also suggest that accumulation of barium and strontium ions in the recharge water infiltrating through the till probably requires a residence time longer than the maximum esidence time measurable by tritium (approximately 50 years)

Northeastern Goodhue County and Major River Valleys. Little or no glacial ediment cover and no bedrock confining units at the surface characterize these areas. Eleven of the 26 samples from these areas were located in major river valleys and contain concentrations of tritium indicating vintage or mixed water. As shown on Plates 7 and 8, these valleys are important discharge areas for bedrock aquifers. Strong upward and lateral flow may have brought older and deeper water near the surface in these areas. In some places, mixing of waters with recent and vintage concentrations of tritium probably occurs where local shallow flow systems converge with the deeper systems creating mixed water (see Plate 8, left portion of D–D' and right portion of E-E'). In other places, all or most of the water intercepted by the wells is vintage water discharging to the river systems. Recent water (six samples) was detected where the wells are too shallow or far from the deep discharging flow systems. Elevated nitrate values (1.1 ppm to 5.1 ppm) were detected in seven of the

recent and mixed water samples. The common occurrences of vintage and mixed concentrations of tritium in these two areas may seem inconsistent with the high to very high sensitivity rating. lowever, the data distribution seemed somewhat biased toward sampling in the major river valleys. Furthermore, ample evidence exists in the data set of mixing occurring in the shallow local flow systems that can be affected by contamination. Therefore, the high to very high rating is justified based on the sensitivity of the shallow flow systems.

GALENA AQUIFER SENSITIVITY

The sensitivity of the Galena aquifer is considered separately for two reasons: it is an areally extensive perched aquifer above the Decorah-Platteville-Glenwood onfining unit and the extent of the Galena Group and associated aquifer is limited to erosional remnants on the Decorah plateau. Therefore, the dynamics of deep and shallow flow systems discussed in the previous section mostly do not apply to the

Measured water levels from wells completed in the Galena aquifer range from about 20 feet to 70 feet below the land surface. At these shallow depths, the Galena aquifer is probably the water table or is connected with the water table in many places. Five water samples were collected from the Galena aquifer for tritium analysis. Three samples contained recent water, one contained mixed water, and one contained vintage water. Two of the samples contained elevated nitrate concentrations (8.4 ppm and 17 ppm). Four of the five samples also contained elevated concentrations of chloride. These data suggest a high sensitivity rating for the Galena aquifer. However, till cover. These sample locations may have biased the sample set toward the high sensitivity range. Some portions of the Galena aquifer farther inward from the edge of the thick till cover may have a lower sensitivity as suggested by the vintage water sample with a carbon-14 age date of 10,000 years old that was drawn from a well east of Kenyon.

Of the 14 water samples that contained elevated chloride concentrations within the county, nine of them were from well locations on or near the Decorah plateau. This relationship suggests that the Galena aquifer and associated glacial till on the Decorah plateau are an important reservoir of ground water containing elevated chloride concentrations. Since much of this chloride probably results from human activities, this high chloride area may be due to a higher production of water effluent with high chloride concentrations on the plateau. A more likely explanation is the longer residence time of ground water on the plateau. As discussed on Plates 7 and vertical recharge of ground water is impeded in this area by the low vertical ydraulic conductivity of the Decorah-Platteville-Glenwood confining unit, which forces infiltrating ground water to travel a longer and slower route through the Galena or till toward the edges of the plateau. In other portions of the county where the upper aquifer is relatively free of chloride, ground-water residence times may be much shorter and essentially flush the chloride to the stream discharge areas.

REFERENCES CITED

Ekman, J., and Alexander, S., 2002, Water chemistry and residence time, technical appendix to Part B in Regional Hydrologic Assessment Otter Tail Area, West-Central Minnesota: Minnesota Department of Natural Resources Regional Hydrogeologic Assessment Series RHA-5, Part B.

Geologic Sensitivity Workgroup, 1991, Criteria and guidelines for assessing geologic

sensitivity of ground water resources in Minnesota: St. Paul, Minnesota,

Department of Natural Resources, Division of Waters, 122 p. indgren, R.L., 2001 Ground-water recharge and flowpaths near the edge of the Decorah-Platteville-Glenwood confining unit, Rochester, Minnesota: U.S. Geological Survey Water-Resources Investigations Report 00-4215.

rating where the Decorah-Platteville-Glenwood confining unit is absent. Aquifer sensitivity should be rated low (light green) where a thick till layer overlies the eroded edge of the Decorah-Platteville-Glenwood confining unit. edge of the Decorah-Platteville-Glenwood confining unit. bromide ratios greater than 10,000 to 1. The chloride to bromide ratios derived from water samples collected from the sensitivity target (uppermost bedrock) aquifers

Decorah-Platteville-Glenwood confining unit is absent. Moderate sensitivity is shown if alluvium overlies the eroded